MSR10 8 8 4 0

(NUMBER TO BE ASSIGNED BY STATE)

APPLICANT IS THE: OWNER PRIME CONTRACTOR	
OWNER CONTACT INFORMATION	
OWNER CONTACT PERSON: Shariq Shamsuddin	
OWNER COMPANY LEGAL NAME: RAN Management	
OWNER STREET OR P.O. BOX: 319 Poplar View LN. W. #1	
OWNER CITY: Collerville STATE: TN	ZIP: 38017
OWNER PHONE #: (901) 590-2877 OWNER EMAIL: davn.ranmanagemen	nt@gmail.com
PREPARER CONTACT INFORMATION	
IF NOI WAS PREPARED BY SOMEONE OTHER THAN THE APPLICANT	
CONTACT PERSON: Byron Houston	
COMPANY LEGAL NAME: Houston Engineering, PLLC.	
STREET OR P.O. BOX: P.O. Box 3087	0055
CITY: Oxford STATE: Mississippi ZIP: 3	8655
PHONE # () 662-647-1312 EMAIL: Byron@HoustonEngr.com	
PRIME CONTRACTOR CONTACT INFORMATION	
PRIME CONTRACTOR CONTACT PERSON: TBD	
PRIME CONTRACTOR COMPANY LEGAL NAME:	
PRIME CONTRACTOR STREET OR P.O. BOX:	
PRIME CONTRACTOR CITY:STATE:	ZIP:
PRIME CONTRACTOR PHONE #: () PRIME CONTRACTOR EMAIL:	
FACILITY SITE INFORMATION	
FACILITY SITE NAME: HWY 178 FUEL CENTER	
FACILITY SITE ADDRESS (If the physical address is not available, please indicate the nearest named reindicate the beginning of the project and identify all counties the project traverses.) STREET: 7740 HWY 178	oad. For linear projects
CITY: Olive Branch STATE: Mississippi COUNTY: Desoto	ZIP: 38654
FACILITY SITE TRIBAL LAND ID (N/A If not applicable): N/A	
LATITUDE: degrees minutes seconds LONGITUDE: degrees minutes	seconds
LAT & LONG DATA SOURCE (GPS (Please GPS Project Entrance/Start Point) or Map Interpolation): GPS	
TOTAL ACREAGE THAT WILL BE DISTURBED 1: 7.25	

IS THIS PART OF A LARGER COMMON PLAN OF DEVELOPMENT?	YES	NO
IF YES, NAME OF LARGER COMMON PLAN OF DEVELOPMENT: AND PERMIT COVERAGE NUMBER: MSR10		
ESTIMATED CONSTRUCTION PROJECT START DATE:	2023 - 3 - 1 <u>YYYY-MM-DD</u>	
ESTIMATED CONSTRUCTION PROJECT END DATE:	2024 - 12 - 31 YYYY-MM-DD	
DESCRIPTION OF CONSTRUCTION ACTIVITY: Construction of Roads, Buildings, Parking and Utilities.		
PROPOSED DESCRIPTION OF PROPERTY USE AFTER CONSTRUCTION HAS BEEN C	OMPLETED:	
SIC Code: 5 4 1 1 NAICS Code 4 4 5 1 2 0		
NEAREST NAMED RECEIVING STREAM: John's Creek		
IS RECEIVING STREAM ON MISSISSIPPI'S 303(d) LIST OF IMPAIRED WATER BODIES? (The 303(d) list of impaired waters and TMDL stream segments may be found on M http://www.deq.state.ms.us/MDEQ.nsf/page/TWB Total_Maximum_Daily_Load_Section)	YES DEQ's web site:	NQ
HAS A TMDL BEEN ESTABLISHED FOR THE RECEIVING STREAM SEGMENT?	YES	NO
FOR WHICH POLLUTANT:		
ARE THERE RECREATIONAL STREAMS, PRIVATE/PUBLIC PONDS OR LAKES WITHIN $rac{1}{2}$ MILE DOWNSTREAM OF PROJECT BOUNDRY THAT MAY BE IMPACTED ACTIVITY?	YES BY THE CONST	NO RUCTION
EXISTING DATA DESCRIBING THE SOIL (for linear projects please describe in SWPPP):		
WILL FLOCCULANTS BE USED TO TREAT TURBIDITY IN STORM WATER?	YES	NO
IF YES, INDICATE THE TYPE OF FLOCCULANT. ANIONIC POLYACRYL OTHER	IMIDE (PAM)	<u> </u>
IF YES, DOES THE SWPPP DESCRIBE THE METHOD OF INTRODUCTION, THE LOCA AND THE LOCATION OF WHERE FLOCCULATED MATERIAL WILL SETTLE?	TION OF INTRO	DUCTION
IS A SDS SHEET INCLUDED FOR THE FLOCCULATE?	YES	Nd
WILL THERE BE A 50 FT BUFFER BETWEEN THE PROJECT DISTURBANCE AND TH STATE?	E WATERS OF THE YES	HE N(
IF NOT, PROVIDE EQUIVALENT CONTROL MEASURES IN THE SWPPP.		

¹Acreage for subdivision development includes areas disturbed by construction of roads, utilities and drainage. Additionally, a housesite of at least 10,000 ft² per lot (entire lot, if smaller) shall be included in calculating acreage disturbed.

DOCUMENTATION OF COMPLIANCE WITH OTHER REGULATIONS/REQUIREMENTS COVERAGE UNDER THIS PERMIT WILL NOT BE GRANTED UNTIL ALL OTHER REQUIRED MDEQ PERMITS AND APPROVALS ARE SATISFACTORILY ADDRESSED

IS LCNOI FOR A FACILITY THAT WILL REQUIRE OTHER PERMITS? YES NO.	
IF YES, CHECK ALL THAT APPLY: AIR HAZARDOUS WASTE PRETREATMENT	
WATER STATE OPERATING INDIVIDUAL NPDES OTHER:	
IS THE PROJECT REROUTING, FILLING OR CROSSING A WATER CONVEYANCE VES NO OF ANY KIND? (If yes, contact the U.S. Army Corps of Engineers' Regulatory Branch for permitting requirements.)	
IF THE PROJECT REQUIRES A CORPS OF ENGINEER SECTION 404 PERMIT, PROVIDE APPROPRIATE DOCUMENTATION THAT:	
-The project has been approved by individual permit, or -The work will be covered by a nationwide permit and NO NOTIFICATION to the Corps is required, or -The work will be covered by a nationwide or general permit and NOTIFICATION to the Corps is required	
IS THE PROJECT REROUTING, FILLING OR CROSSING A STATE WATER CONVEYANCE YES OF ANY KIND? (If yes, please provide an antidegradation report.)	0 🗸
IS A LAKE REQUIRING THE CONSTRUCTION OF A DAM BEING PROPOSED? (If yes, provide appropriate approval documentation from MDEQ Office of Land and Water, Dam Safety.)	0 🗸
IF THE PROJECT IS A SUBDIVISION OR A COMMERCIAL DEVELOPMENT, HOW WILL SANITARY SEWA BE DISPOSED? Check one of the following and attach the pertinent documents.	GE
Existing Municipal or Commercial System. Please attach plans and specifications for the collection system and associated "Information Regarding Proposed Wastewater Projects" form or approval from County Utility Author Hancock, Harrison, Jackson, Pearl River and Stone Counties. If the plans and specifications can not be provided at the of LCNOI submittal, MDEQ will accept written acknowledgement from official(s) responsible for wastewater collection and treatment that the flows generated from the proposed project can and will be transported and tre properly. The letter must include the estimated flow.	ity in ie time
Collection and Treatment System will be Constructed. Please attach a copy of the cover of the NPDES discharge permit from MDEQ or indicate the date the application was submitted to MDEQ (Date:	:)
Individual Onsite Wastewater Disposal Systems for Subdivisions Less than 35 Lots. Please attach a copy of the I of General Acceptance from the Mississippi State Department of Health or certification from a registered profesengineer that the platted lots should support individual onsite wastewater disposal systems.	Letter ssional
Individual Onsite Wastewater Disposal Systems for Subdivisions Greater than 35 Lots. A determination of the feasibility of installing a central sewage collection and treatment system must be made by MDEQ. A copy of the response from MDEQ concerning the feasibility study must be attached. If a central collection and wastewater is not feasible, then please attach a copy of the Letter of General Acceptance from the State Department of Heal certification from a registered professional engineer that the platted lots should support individual onsite waster disposal systems.	system th or
INDICATE ANY LOCAL STORM WATER ORDINANCE (I.E. MS4)WITH WHICH THE PROJECT MUST COM	PLY:

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature of Applicant Jowner or prime contractor)

Date Signed

Amanullah Penji

Pevji

C-member

Title

¹This application shall be signed as follows:

- For a corporation, by a responsible corporate officer.
- · For a partnership, by a general partner.
- For a sole proprietorship, by the proprietor.

For a municipal, state or other public facility, by principal executive officer, mayor, or ranking elected official

Please submit the LCNOI form to:

Chief, Environmental Permits Division

MS Department of Environmental Quality, Office of Pollution Control

P.O. Box 2261

Jackson, Mississippi 39225

Electronically:

https://www.mdeq.ms.gov/construction-stormwater/

Revised 3/23/22

HOUSTON ENGINEERING Engineering, Surveying, and Environmental Services

1207 Office Park Dr., Suite B Oxford, Mississippi 38655 Office: (662) 205-6653

Cell: (662) 647-1312 E-mail: byron@houstonengr.com

October 27, 2022

Mississippi Department of Environmental Quality 515 East Amite St. Jackson, MS 39201

RE: HWY 178 FUEL CENTER 7740 HWY 178 Olive Branch, MS 38654

Dear Sir or Madam:

Please review the enclosed referenced project for approval of the LCNOI. Attached you will find the signed LCNOI, Site Quad Map, Civil Site Plans as well as a SWPPP Narrative. Please advise if anything further is needed in order to gain approval.

Sincerely, HOUSTON ENGINEERING

J. Byron Houston, P.E., P.S. Sr. Project Manager



LARGE CONSTRUCTION NOTICE OF INTENT (LCNOI) FOR COVERAGE UNDER THE LARGE CONSTRUCTION STORM WATER GENERAL NPDES PERMIT

INSTRUCTIONS

The Large Construction Notice of Intent (LCNOI) is for coverage under the Large Construction General Permit for land disturbing activities of five (5) acres or greater; or for land disturbing activities, which are part of a larger common plan of development or sale that are initially less than five (5) acres but will ultimately disturb five (5) or more acres. Applicant must be the owner or operator. For construction activities, the operator is typically the prime contractor. The owner(s) of the property and the prime contractor associated with regulated construction activity on the property have joint and severable responsibility for compliance with the Large Construction Storm Water General Permit MSR10.

If the company seeking coverage is a corporation, a limited liability company, a partnership, or a business trust, attach proof of its registration with the Mississippi Secretary of State and/or its Certificate of Good Standing. This registration or Certificate of Good Standing must be dated within twelve (12) months of the date of the submittal of this coverage form. Coverage will be issued in the company name as it is registered with the Mississippi Secretary of State.

Completed LCNOIs should be filed at least thirty (30) days prior to the commencement of construction. Discharge of storm water from large construction activities without written notification of coverage is a violation of state law.

Submittals with this LCNOI must include:

- A site-specific Storm Water Pollution Prevention Plan (SWPPP) developed in accordance with ACT5 of the General Permit
- A detailed site-specific scaled drawing showing the property layout and the features outlined in ACT5 of the General Permit
- A United States Geological Survey (USGS) quadrangle map or photocopy, extending at least one-half mile beyond the facility property boundaries with the site location and outfalls outlined or highlighted. The name of the quadrangle map must be shown on all copies. Quadrangle maps can be obtained from the MDEQ, Office of Geology at 601-961-5523.

Additional submittals may include the following, if applicable:

- · Appropriate Section 404 documentation from U.S. Army Corps of Engineers
- Appropriate documentation concerning future disposal of sanitary sewage and sewage collection system construction
- Appropriate documentation from the MDEQ Office of Land & Water concerning dam construction and low flow requirements
- · Approval from County Utility Authority in Hancock, Harrison, Jackson, Pearl River and Stone Counties
- Antidegradation report for disturbance within Waters of the State

ALL QUESTIONS MUST BE ANSWERED (Answer "NA" if the question is not applicable)

QUAD MAP



DESOTO COUNTY, MISSISSIPPI

SCALE: 1" = 2000'

Produced by the United States Geological Survey

North American Datum of 1983 (NAD83)
World Geodetic System of 1984 (WGS84). Projection and
1 000-meter grid:Universal Transverse Mercator, Zone 16S
This map is not a legal document. Boundaries may be
generalized for this map scale. Private lands within government
reservations may not be shown. Obtain permission before

Imagery		ΝΔΙΡ	lune 2016	- October	2016
Roads	ι	J.S. Census	Bureau,	2016 -	2017
Names			G	NIS, 1980 -	2020
Hydrography	Natio	nal Hydrogra	phy Dataset	, 2004 -	2018
Contours		National Ele	vation Datas	et, 2012 -	2019
BoundariesMultiple	sources;	see metad	ata file	2018 -	2019
Public Land Survey Syste	m			BLM,	2017
WetlandsFWS	National	Wetland	s Inve	ntory	1980



ROAD CLASSIFICATION

Expressway			Local Conne	ector
Secondary Hwy			Local Road	
Ramp			4WD	
Interstate	Route	US	Route	State Route

DATE: 10/18/22 DWG: 222-157.015



entering private lands.

HOUSTON ENGINEERING

Engineering, Surveying, and Environmental Services

P.O. Box 3087 Oxford, Mississippi 38655

Phone: (662) 647-1312 E-mail: byron@houstonengr.com


HENLEY SUBDIVISION

9.89 ACRES IN THE NE \$\frac{1}{4}\$ OF SECTION 20, TOWNSHIP 1 SOUTH, RANGE 6 WEST, DESOTO COUNTY, MS

DESOTO COUNTY STATE OF MISSISSIPPI

NOT TO SCALE

PLANS FOR THE CONSTRUCTION OF HWY 178 FUEL CENTER 7740 HIGHWAY 178, OLIVE BRANCH, MS, 38654



SCALE: 1" = 2000'

INDEX

LOCATION AND INDEX G1.0 **GENERAL NOTES** TRAFFIC CONTROL PLAN G3.0-G3.1 TYPICAL SECTIONS G4.0-4.2 SITE TOPOGRAPHICAL SURVEY SITE DEMOLITION PLAN C2.0 SITE LAYOUT PLAN C3.0 OVERALL GRADING PLAN C4.0 **ENLARGED GRADING PLAN** C4.1-C4.2 OVERALL DRAINAGE PLAN C5.0 **ENLARGED DRAINAGE PLAN** C5.1-C5.2 NEW CRAFT ROAD PLAN & PROFILE C6.0 C6.1 HWY 178 PLAN & PROFILE C7.0 SITE UTILITY PLAN SANITARY SEWER PLAN & PROFILE C7.1 SITE PAVING PLAN C8.0 SITE EROSION CONTROL PLAN C9.0 **EROSION CONTROL DETAILS** D1.0 HANDICAP PARKING DETAILS D2.0 SIDEWALK & PAVING DETAILS D3.0 D4.0 MISCELLANEOUS DETAILS **SANITARY SEWER DETAILS** D5.0 WATER DISTRIBUTION DETAILS D6.0 D7.0 **OUTLET CONTROL STRUCTURE DETAIL** D8.0 TYPE B SILT BASIN DETAIL

ENGINEER:

TO THE OWNER.



DIGGING. THE CONTRACTOR SHALL REPAIR OR REPLACE THE

ABOVE WHEN DAMAGED DURING CONSTRUCTION AT NO COST

DEVELOPER:

RAN MANAGMENT COMPANY, LLC 319 POPLAR VIEW LN. W. #1 COLLERVILLE, TN 38017

SHEET NUMBER:

HE JOB NO. 222-157.015 **REV A - ISSUE FOR REVIEW** G1.0

TO ESTABLISH THE COMPLETE SCOPE OF ITS WORK AND TO EFFECT CLOSE COORDINATION WITH THE OTHER TRADES, EACH TRADE SHALL COMPLETELY REVIEW THE PLANS AND SPECIFICATIONS, NOT ONLY FOR ITS RESPECTIVE TRADE, BUT FOR THE WORK OF THE OTHER RELATED TRADES AS WELL. TITLES OF DIVISIONS (AND SECTIONS IN SPECIFICATIONS) IDENTIFYING WORK ARE PROVIDED FOR ORGANIZATIONAL AND REFERENCE PURPOSES AND SHALL NOT BE TAKEN AS AN ABSOLUTE SEPARATION OF THE TRADES OR OF THE UNITS OF MATERIAL AND LABOR.

THE CONTRACTOR SHALL COORDINATE AND OBTAIN ALL NECESSARY PERMITS AND APPROVALS OR GUIDELINES FROM GOVERNING REGULATORY AGENCIES BEFORE PROCEEDING WITH ANY ITEMS OF WORK UNDER OR WITHIN SUCH JURISDICTION(S).

ALL DIMENSIONS AND TIE-INS GOVERNED BY EXISTING CONDITIONS ARE APPROXIMATE AND ARE NOT GUARANTEED TO BE CORRECT. ALL SUCH DIMENSIONS AND CONDITIONS SHALL BE FIELD VERIFIED BY WILL BE MADE FOR REPLACEMENT OR REPAIR OF DAMAGED ITEMS. THE GENERAL CONTRACTOR PRIOR TO PROCEEDING WITH ANY WORK. IF CONDITIONS AND DIMENSIONS VARY FROM THOSE SHOWN, THE CONTRACTOR SHALL NOTIFY THE ENGINEER BEFORE PROCEEDING WITH WORK WHERE DIMENSIONS ARE NOT SHOWN WITH +/- INDICATIONS ADJUSTMENTS MAY BE MADE TO SUIT FIELD CONDITIONS.

- THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS, LOCATION OF UTILITY SERVICES, DIMENSIONS, AND ELEVATIONS OF SITE AND ANY DATA REQUIRED TO CONSTRUCT THE PROJECT.
- THE CONTRACTOR SHALL SUBCONTRACT WITH SUPPLIERS, FABRICATORS AND INSTALLATION COMPANIES WHICH CAN DEMONSTRATE THEY POSSESS THE KNOWLEDGE, EXPERIENCE, AND PROVEN CAPABILITIES TO FULLY PERFORM ALL ASPECTS OF THE WORK REQUIRED WITHOUT OMISSION.
- UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE PLOTTED IN THEIR APPROXIMATE LOCATIONS FROM THE BEST INFORMATION AVAILABLE TO THE ENGINEER. THE ENGINEER DOES NOT GUARANTEE THEIR ACCURACY OR GUARANTEE THAT ALL UTILITIES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES, INCLUDING ANY SUBSURFACE INVESTIGATIONS, AS MAY BE NECESSARY BEFORE ANY EXCAVATION IS PERFORMED. CONTRACTOR SHALL BE REQUIRED TO CALL 811 AT LEAST 48-HOURS BEFORE START OF WORK.
- THE CONTRACTOR SHALL CALL 811 48-HOURS BEFORE ANY EXCAVATION ACTIVITIES BEGIN TO HAVE UTILITIES LOCATED IN ACCORDANCE WITH STATE LAW. THE CONTRACTOR IS RESPONSIBLE FOR

THE CONTRACTOR IS RESPONSIBLE FOR SAFETY ON THE PROJECT. THE CONTRACTOR SHALL FOLLOW ALL INDUSTRY STANDARDS TO INSURE A SAFE WORKING ENVIRONMENT FOR EMPLOYEES AND SITE 40. WATER SERVICE & SANITARY SEWER SHALL BE PROVIDED BY CITY OF OLIVE BRANCH. OWNER WILL BE RESPONSIBLE FOR ALL CONNECTION FEES. WATER AND SANITARY SEWER SERVICE LINES SHALL BE VISITORS.

- SILT AND SEDIMENTATION CONTROL SHALL CONSIST OF INSTALLATION OF TEMPORARY SILT FENCES, HAY BALES, TEMPORARY OR INTERIM GRASSING, SUMPS AND OTHER PRUDENT CONSTRUCTION METHODS. SILT FENCES AND HAY BALES SHALL BE INSTALLED AT THE DIRECTION OF THE ENGINEER AND PAID FOR UNDER APPLICABLE PAY ITEMS. COST OF TEMPORARY GRASSING, SUMPS, AND OTHER
- EROSION CONTROL MEASURES SHALL BE PLACED ON ALL AREAS AS SOON AS POSSIBLE DURING CONSTRUCTION.
- 11. DURING CONSTRUCTION OPERATIONS THE CONTRACTOR SHALL HAVE PROPER EQUIPMENT ON SITE TO ENSURE SUFFICIENT COMPACTION OF ALL COURSES (LAYERS) I.E.; SHEEPS FOOT ROLLER, PNEUMATIC RUBBER TIRE OR STEEL ROLLER(S), FARM TRACTOR(S) WITH DISK, DOZER(S), WATER TRUCK AND ROAD GRADER(S).
- 12. NO COURSE (LAYER) SHALL BE COVERED WITHOUT APPROVAL FROM THE ENGINEER REGARDLESS OF RESULTS FROM DENSITY TEST.
- 13. COURSE (LAYERS) SHALL NOT EXCEED 8 INCH LIFTS.
- 14. IF DETERMINED BY THE ENGINEER THAT IN-PLACE MATERIALS ARE TOO WET, DUE TO WEATHER, ALL HAULING OPERATIONS SHALL BE HALTED.
- 15. EACH COURSE (LAYER) SHALL BE SHAPED TO REQUIRED SECTION, WATERED OR AERATED AS NECESSARY TO PRODUCE THE REQUIRED MOISTURE AND COMPACTION THROUGHOUT THE OPERATION.
- 16. PIPE LENGTHS SHOWN ARE APPROXIMATE AND MAY BE ADJUSTED AS REQUIRED.

DEVICES, TO REDUCE SILTATION, SHALL BE ABSORBED INTO OTHER ITEMS.

- 17. THE CONTRACTOR SHALL REPLACE ALL PAVING, STABILIZED EARTH, CURBS, DRIVEWAYS, SIDEWALKS, ETC. WITH MATERIALS OF THE SAME TYPE OR BETTER THAN THAT REMOVED DURING CONSTRUCTION. HEREOF FULLY AND COMPLETELY AS IF ATTACHED HERETO, EXCEPT WHERE SUPERCEDED BY THE SPECIAL PROVISIONS, OR AMENDED BY REVISIONS.
- 18. LAY PIPE TO UNIFORM GRADE, AS SHOWN ON PLANS. PIPE DEFLECTION SHALL NOT EXCEED 75% OF MAXIMUM RECOMMENDED.
- 19. SIZE OF FITTINGS, TYPES OF JOINTS, AND FITTING MATERIALS SHOWN ON PLANS SHALL CORRESPOND TO ADJACENT STRAIGHT RUN OF PIPE UNLESS OTHERWISE INDICATED.

DAMAGES TO ALL UTILITIES DURING CONSTRUCTION. IF UTILITIES ARE DAMAGED THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE UTILITY INVOLVED IMMEDIATELY.

- 20. ALL BURIED PIPING SHALL BE TESTED AS SPECIFIED.
- 21. PRIOR TO ORDERING MATERIALS, THE CONTRACTOR SHALL VERIFY ALL EXISTING LINE SIZES.
- 22. COORDINATES FOR THIS PROJECT ARE REFERENCED TO THE NAD83 MISSISSIPPI STATE PLANE COORDINATE SYSTEM, EAST ZONE (2301), THE CONTROL AND TEMPORARY BENCHMARKS WERE ESTABLISHED USING A G.P.S. NETWORK ROVER OPERATING ON THE USM CONTINUOUS OPERATING REFERENCE STATION (CORS) NETWORK. ÉLEVATIONS ARE NAVD88 AND WERE DERIVED USING GEOID MODEL
- 23. CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING, PROTECTING, REPAIRING, AND REPLACING AS NECESSARY, ALL UTILITY BOXES, INLET GRATES, VALVE BOXES, MANHOLE LIDS, SANITARY FORCE MAINS OR SERVICES, ETC. THAT ARE DISTURBED WITHIN THE AREA OF WORK.
- 24. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION WITH UTILITY COMPANIES. ALL UTILITY POLES IN CLOSE PROXIMITY TO PROPOSED LINEWORK SHALL BE HELD IN PLACE UNTIL PROPER COMPACTION IS ACHIEVED. THIS ITEM IS TO BE COVERED UNDER MOBILIZATION / DEMOBILIZATION
- 25. THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UTILITIES ON THE PROJECT SITE, AND SHALL PROMPTLY REPAIR THOSE WHICH ARE DAMAGED BY HIS CONSTRUCTION OPERATIONS. BEFORE 54. ANY LOCAL, STATE, OR FEDERAL PERMITTING REQUIRED FOR CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. DIGGING, CONTRACTOR SHALL CONTACT MISSISSIPPI ONE-CALL AT 1-800-227-6477.
- 26. THE CONTRACTOR MUST HAVE WRITTEN APPROVAL FROM THE OWNER AND/OR PROJECT ENGINEER OF RECORD BEFORE ANY CHANGE IN THE DESIGN IS MADE.
- 27. CONTRACTOR SHALL PROVIDE A MINIMUM 24 HOUR NOTICE TO THE ENGINEER PRIOR TO COMMENCING ANY CONSTRUCTION OPERATIONS, SAMPLING, OR TESTING
- 28. ALL FILL LIFTS IN AREAS BENEATH FUTURE ROADWAYS AND BUILDINGS SHALL BE COMPACTED TO 95% OF THE STANDARD PROCTOR DENSITY (ASTM D-698) AT A MOISTURE CONTENT WITHIN 2 PERCENTAGE POINTS OF OPTIMUM MOISTURE, AND 90% OF THE STANDARD PROCTOR DENSITY IN AREAS OUTSIDE OF BUILDING LIMITS, WITH THE SAME MOISTURE CONTENT REQUIREMENTS. FILL MATERIAL MUST BE DETERMINED TO BE SUITABLE BY A CERTIFIED TESTING LABORATORY. FOR ALL FILL AREAS, STABILITY MUST BE EVIDENT AT EACH LIFT BEFORE SUBSEQUENT LIFTS ARE PLACED. MAXIMUM LOOSE LIFT₅₇. CONTRACTOR SHALL PROVIDE PROPER TRAFFIC CONTROL (SIGNS, BARRICADES, FLAGMEN, ETC.) WHEN WORKING WITHIN PUBLIC RIGHT-OF-WAYS. APPROPRIATE AUTHORITIES SHALL BE NOTIFIED AT TO BE 9". IN ADDITION TO DENSITY REQUIREMENTS, THE FINAL LIFT OF FILL MATERIAL SHALL BE PROOF-ROLLED WITH A LOADED TANDEM-AXLE TRUCK TO DEMONSTRATE STABILITY AFTER COMPACTION REQUIREMENTS HAVE BEEN ACHIEVED. GEOTECHNICAL REPORT RECOMMENDATIONS SHALL TAKE PRECEDENCE OVER ITEMS SHOWN IN THE PLANS AND SPECIFICATIONS.
- 29. CONTRACTOR SHALL TAKE WHATEVER STEPS NECESSARY TO ENSURE THAT POSITIVE DRAINAGE OCCURS ON ALL AREAS OF PROJECT SITE DURING ALL STAGES OF CONSTRUCTION.
- 30. THE CONTRACTOR IS REQUIRED TO REMOVE ALL SPOIL MATERIAL ON A DAILY BASIS.
- 31. AT THE EXPENSE OF THE CONTRACTOR, THE CONTRACTOR SHALL MAINTAIN EXISTING DRAINAGE PATTERNS AND CONSTRUCT TEMPORARY STRUCTURES, EMBANKMENTS, AND CULVERTS AS REQUIRED TO MAINTAIN THE EXISTING DRAINAGE SYSTEM AND CAPACITY IN THE WORK AREA. ANY AND ALL TEMPORARY STRUCTURES, EMBANKMENTS, AND CULVERTS CONSTRUCTED DURING THE PROGRESS OF WORK SHALL BE REMOVED IF NOT NECESSARY FOR FINAL DRAINAGE SYSTEM AND THE AREA RESTORED TO ITS ORIGINAL CONDITION.
- 32. THE CONTRACTOR SHALL FURNISH, PLACE, AND MAINTAIN ALL SHEETING, SHORING, AND BRACING REQUIRED TO SUPPORT THE SIDES OF THE REQUIRED TRENCH EXCAVATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SUFFICIENCY OF ANY SUCH SUPPORTS TO PREVENT ANY MOVEMENT WHICH CAN IN ANY WAY DAMAGE OR DELAY THE WORK; ENDANGER OR CAUSE DAMAGE TO ADJACENT PAVEMENTS, BUILDINGS, OR OTHER STRUCTURES; OR CREATE UNDUE HAZARDS TO WORKMEN. ALL EXCAVATIONS SHALL BE MADE AND KEPT IN COMPLIANCE WITH THE U.S. DEPARTMENT OF LABOR

- OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS (Z9CFR, 1926 SUBPART P)
- 33. THE LOCATION, RIM, AND INVERT ELEVATIONS OF PROPOSED GRATE INLETS AND SEWER MANHOLES IS BASED ON DESIGN ROADWAY AND EARTHWORK GRADES. ANY CHANGES OR DEVIATIONS FROM THE FINISHED ROAD GRADES MAY REQUIRE ADJUSTMENTS TO THE RIM AND INVERT ELEVATIONS OF PREVIOUSLY MENTIONED STRUCTURES. COORDINATES SHOWN FOR DRAINAGE STRUCTURES AND SEWER MANHOLES ARE REFERENCED TO THE CENTER OF THE STRUCTURE.
- 34. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT EXISTING STRUCTURES THAT ARE TO REMAIN SUCH AS PIPES, INLETS, AND PAVED DITCHES, ETC. FROM DAMAGE WHICH MIGHT OCCUR DURING CONSTRUCTION. THE CONTRACTOR SHALL REPLACE OR REPAIR, AS DIRECTED BY THE ENGINEER, ANY STRUCTURES DAMAGED DURING THE LIFE OF THE CONTRACT. NO PAYMENT TO CONTRACTOR
- 35. CONTRACTOR SHALL RETAIN A SET OF RECORD DRAWINGS DURING CONSTRUCTION WITH LEGIBLE DIMENSIONS AND NOTES THAT RECORD ACTUAL CONSTRUCTION. AT PROJECT CLOSEOUT, CONTRACTOR SHALL RETURN THE RECORD DRAWINGS TO THE ENGINEER.
- 36. VOIDS CREATED BY THE REMOVAL OF POSTS, CONCRETE ANCHORS, FOOTINGS, AND PIPES, ETC. SHALL BE BACKFILLED AND TAMPED IN ACCORDANCE WITH THE SPECIFICATIONS. COST TO BE ABSORBED BY CONTRACTOR.
- 37. THE COSTS OF STANDARD ROADSIDE SIGN POSTS SHALL BE INCLUDED IN THE PROJECT CONTRACT PRICE. CONTRACTOR SHALL VERIFY POST LENGTHS PRIOR TO FABRICATION. ROADSIDE SIGNS SHALL CONFORM TO THE LATEST "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD).
- 38. BEFORE FINAL ACCEPTANCE, ENTIRE RIGHT-OF-WAY SHALL BE MOWED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- 39. NO CONSTRUCTION ACTIVITIES SHALL COMMENCE UNTIL ALL APPROVALS AND PERMITS HAVE BEEN OBTAINED FROM GOVERNING AUTHORITIES (INCLUDING BUT NOT LIMITED TO CITY, COUNTY, MS DEPARTMENT OF HEALTH, MDEQ, MDOT, CORPS OF ENGINEERS, UTILITY ASSOCIATIONS). ANY WORK PERFORMED PRIOR TO OBTAINING SAID PERMITS AND APPROVALS SHALL OCCUR AT THE RISK OF THE CONTRACTOR AND/OR OWNER.
- INSTALLED BY THE CONTRACTOR AS SHOWN IN THE PLANS AND STANDARD DETAILS ATTACHED.
- 41. CONTRACTOR SHALL CONTACT THE CITY ENGINEER TWENTY-FOUR (24) HOURS PRIOR TO PROOF-ROLLING.
- 42. HIGH DENSITY POLYETHYLENE PIPE (HDPE) SHALL HAVE A FULL CIRCULAR CROSS-SECTION, AND SHALL BE CORRUGATED ON THE EXTERIOR AND SMOOTH LINED ON THE INTERIOR AND SHALL BE MANUFACTURED IN ACCORDANCE WITH REQUIREMENTS OF AASHTO M 294 AND AASHTO MP7, LATEST EDITIONS. PIPE AND FITTINGS SHALL BE MANUFACTURED FROM VIRGIN PE COMPOUNDS WHICH CONFORM TO THE REQUIREMENTS OF CELL CLASS 335400C AS DEFINED AND DESCRIBED IN ASTM D 3350. ALL HDPE DELIVERED AND USED SHALL BE CERTIFIED THROUGH THE PLASTICS PIPE INSTITUTE (PPI) THIRD PARTY CERTIFICATION PROGRAM, AND SHALL BEAR THE THIRD PART ADMINISTERED PPI SEAL. BEDDING MATERIAL SHALL BE REQUIRED FOR ALL HDPE PIPE, TO THE DIMENSIONS DETAILED ON THE CONSTRUCTION
- 43. ALL R1-1 REFLECTORIZED STOP SIGNS SHALL BE PROVIDED WITH HIGH INTENSITY PRISMATIC SHEETING MEETING BOTH ASTM D4956-09 TYPE III, TYPE IV, AND ASTM D4956-07 TYPE X SPECIFICATIONS AND SHALL INCLUDE CERTIFICATION WITH DATE OF INSTALLATION.
- 44. CONCRETE PIPE JOINTS SHALL BE RUBBER GASKET COMPLYING WITH ASTM C-443 AS SPECIFIED. ALL CONCRETE PIPE WITH RUBBER GASKETS, WRAPPED JOINTS AND PIPITS SHALL BE COVERED WITH TYPE V FILTER FABRIC.
- 45. CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO ANY CONSTRUCTION THAT MAY DAMAGE TREES, WHICH ARE NOT MARKED OR INDICATED ON THE DRAWINGS TO BE REMOVED.
- 46. CONTRACTOR SHALL STOCK PILE TOPSOIL FOR SUBSEQUENT USE FOR GRASSING AND LANDSCAPING ITEMS.
- .47. MISSISSIPPI STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION CURRENTLY APPROVED (2004 EDITION) BY THE MDOT AND THE FEDERAL HIGHWAY ADMINISTRATION ARE MADE PART
- 48. ANY UTILITIES SUCH AS MANHOLE COVERS, WATER VALVE COVERS, GAS VALVE COVERS, ETC. SHALL BE ADJUSTED TO FINISHED GRADE OF ASPHALT, COST TO BE ABSORBED
- 49. ANY QUANTITIES SHOWN ARE STRICTLY ESTIMATES, AND ARE PROVIDED AS A COURTESY ONLY AND DO NOT RELIEVE THE CONTRACTOR FROM COMPLETING PROJECT AS OUTLINED ON CONSTRUCTION DRAWINGS AND IN TECHNICAL SPECIFICATIONS.
- 50. ALL TOPSOIL WITHIN THE CONSTRUCTION LIMITS SHALL BE STRIPPED, STOCKPILED IN A DESIGNATED AREA TO BE APPROVED BY THE ENGINEER, AND REPLACED ON SLOPES OR AS DIRECTED BY THE ENGINEER. THE COST OF THIS STRIPPING, STOCKPILING, AND REPLACING AFTER GRADING IS COMPLETE WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR STRIPPING. UPON COMPLETION OF GRADING, THE CONTRACTOR SHALL PLACE A SUFFICIENT QUANTITY OF TOPSOIL TO INSURE GRASS GROWTH ON THE DESIGNATED AREA. ANY EXCESS TOPSOIL SHALL REMAIN STOCKPILED FOR FUTURE USE BY THE OWNER.
- 51. SEDIMENT RUNOFF ON ANY AREA DISTURBED BY THE CONTRACTOR WILL BE CONTROLLED AT ALL TIMES. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE MAINTENANCE OF EROSION CONTROL MEASURES USED TO CONTROL SEDIMENT RUNOFF.
- 52. CLEARED AND GRUBBED RUBBISH, AS WELL AS MATERIAL UNSUITABLE FOR USE IN THE FILL, WILL BE DISPOSED OF OFF SITE BY THE CONTRACTOR IN A RESPONSIBLE MANNER. ASSOCIATED COSTS TO BE ABSORBED BY THE CONTRACTOR.
- 53. CONTRACTOR SHALL SEED AND FERTILIZE ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES AND INSURE A COMPLETE STAND OF GRASS.
- 55. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLETING ALL SAMPLING AND TESTING OF MATERIALS INCORPORATED INTO THE PROJECT AND FOR SUBMISSION OF SAME TO THE ENGINEER FOR REVIEW. ALL PHASES OF TESTING, INCLUDING BUT NOT LIMITED TO SAMPLING, TRANSPORTING, AND TESTING OF MATERIALS, MUST BE PERFORMED BY A CERTIFIED TESTING LABORATORY. PRIOR USE TEST RESULTS, MANUFACTURER'S CERTIFICATES, OR PROPOSED MIX DESIGNS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW BEFORE INCORPORATION INTO THE PROJECT. THIS SHALL INCLUDE EMBANKMENT, BACKFILL, SEED, AND ALL OTHER ITEMS SPECIFIED BY THE ENGINEER. ALL COSTS ASSOCIATED WITH TESTING SHALL BE ABSORBED BY THE CONTRACTOR.
- 56. CONSTRUCTION STAKING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, AND SHALL BE ABSORBED BY THE CONTRACTOR.
- LEAST 24 HOURS PRIOR TO COMMENCING ANY CONSTRUCTION OPERATIONS WITHIN PUBLIC RIGHT-OF-WAYS.
- 58. THE PROPERTY PARCEL NUMBER IS 106420000 0002102, ITS ZONED IN M-2 AND IS LOT NUMBER 1. PROPERTY ADDRESS IS 7742 HIGHWAY 178, OLIVE BRANCH, MS, 38645. THE PROPERTY IS 4 ACRES OR 174240.00 SQ.FT.
- 59. CONTACT THE CITY ENGINEER ANDY SWIM AT EMAIL ANDY.SWIMS@OBMS.US
- - WATER CITY OF OLIVE BRANCH (CONTACT (662) 893-5208) SANITARY SEWER - OLIVE BRANCH (CONTACT (662) 893-5208)
 - ELECTRIC POWER NORTH CENTRAL EPA (CONTACT (662) 895-2151) TELECOM - AT&T (1-888-944-0447)
- NATURAL GAS CITY OF OLIVE BRANCH (CONTACT (662) 893-5209)

STO

G2.0

 $A \mid 8/9/22 \mid ISSUE FOR REVIEW$

JBH JBH

GENERAL NOTES:

- 1. ALL SIGNS AND TRAFFIC CONTROL DEVICES SHALL CONFORM TO THE APPLICABLE SPECIFICATIONS OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", LATEST EDITION.
- 2. CONTRACTOR SHALL INSTALL TRAFFIC CONTROL DEVICES SUCH AS SIGNS, BARRICADES, CONES, DRUMS, LIGHTS, FLASHERS, AND PROVIDE FLAGGERS AS REQUIRED TO SAFEGUARD AND DIRECT TRAFFIC. (WHENEVER FLAGGERS ARE USED, INSTALL "FLAGGER AHEAD" SIGN EXCEPT DURING BRIEF PERIODS OR EMERGENCY SITUATIONS.)
- 3. THE SIGNS AND DEVICES REQUIRED HEREON ARE A MINIMUM REQUIREMENT AND IT SHALL BE THE RESPONSIBILTY AND OBLIGATION OF THE CONTRACTOR TO DETERMINE AND PROVIDE ANY ADDITIONAL DEVICES REQUIRED TO SAFEGUARD THE PUBLIC..
- 4. TRAFFIC CONTROL DEVICES SHALL BE INSTALLED WHENEVER NECESSARY, REMAIN IN PLACE AS LONG AS THEY ARE NEEDED, AND BE REMOVED IMMEDIATELY WHEN THE NEED CEASES.
- 5. INSTALLATION OF SIGNS AND BARRICADES SHALL CONFORM TO MDOT STANDARD DRAWING NOS. 6358, 6366, AND 6367.
- 6. CONTRACTOR SHALL INSTALL ADVANCE WARNING SIGNS SUCH AS WATCH FOR TRUCKS, TRUCKS TURNING, TRUCKS CROSSING, ETC., AND PLACE FLAGGERS AS DIRECTED BY THE COUNTY ENGINEER ALONG PUBLIC ROADS ON EACH SIDE OF BORROW PIT ENTRANCE OR CROSSING OF PUBLIC ROADS.

CONSTRUCTION NOTES:


TEMPORARY PAVEMENT MARKINGS. WHENEVER PAVEMENT CONSTRUCTION HAS PROGRESSED SIGNIFICANTLY TO PERMIT TRAFFIC MOVEMENT THAT IS UNRESTRICTED BY CHANNELIZING OR OTHER TRAFFIC CONTROL METHODS, TEMPORARY PAVEMENT MARKINGS SHALL BE INSTALLED. MARKINGS SHALL BE INSTALLED AND MAINTAINED IN A LIKE MANNER AFTER EACH LIFT AND PRIOR TO NIGHTFALL.

- 1. A SHADOW OF VEHICLE SHALL BE POSITIONED APPROXIMATELY 300 FT. IN FRONT OF AND BEHIND PAINTING OPERATIONS.
- 3. A FLASHING YELLOW LIGHT SHALL BE INSTALLED ABOVE THE TOP OF THE WARNING SIGNS.
- 4. A FLASHING YELLOW LIGHT SHALL BE INSTALLED ON ALL VEHICLES USED IN THE MARKING OPERATIONS.

		SIGN SCHEDULE
SIGN	TYPE/DES	SCRIPTION
1	W20-3	"ROAD WORK AHEAD"
2	G20-2	"END ROAD WORK"

HOUSTON ENGINEERING


Engineering, Surveying, and Environmental Services





G3.0

A 8/9/22 ISSUE FOR REVIEW

JBH JBH BY APVD











A 8/9/22 ISSUE FOR REVIEW


JBH JBH BY APVD











8/9/22 ISSUE FOR REVIEW

JBH JBH BY APVD

HOUSTON ENGINEERING


Findingering Surveying and Environmental Services


HWY 178 FUE HWY178, OLIVE E SITE LAYOU





C3.0

SHEET 10 OF 30










SCALE: 1" = 30'

GRADING & DRAINAGE PLAN NOTES:

- 1. THE CONTRACTOR SHALL COORDINATE AND OBTAIN ALL NECESSARY PERMITS AND APPROVALS OR GUIDELINES FROM GOVERNING REGULATORY AGENCIES BEFORE PROCEEDING WITH ANY ITEMS OF WORK UNDER OR WITHIN SUCH JURISDICTION(S).
- 2. ALL DIMENSIONS AND TIE-INS GOVERNED BY EXISTING CONDITIONS ARE APPROXIMATE AND ARE NOT GUARANTEED TO BE CORRECT. ALL SUCH DIMENSIONS AND CONDITIONS SHALL BE FIELD VERIFIED BY THE GENERAL CONTRACTOR PRIOR TO PROCEEDING WITH ANY WORK. IF CONDITIONS AND DIMENSIONS VARY FROM THOSE SHOWN, THE CONTRACTOR SHALL NOTIFY THE ENGINEER BEFORE PROCEEDING WITH WORK WHERE DIMENSIONS ARE NOT SHOWN WITH +/- INDICATIONS ADJUSTMENTS MAY BE MADE TO SUIT FIELD CONDITIONS.
- ${\tt 3.}\ {\tt THE\ CONTRACTOR\ SHALL\ VERIFY\ EXISTING\ CONDITIONS,\ LOCATION\ OF\ UTILITY\ SERVICES,}\\$ DIMENSIONS, AND ELEVATIONS OF SITE AND ANY DATA REQUIRED TO CONSTRUCT THE PROJECT.
- 4. THE CONTRACTOR SHALL SUBCONTRACT WITH SUPPLIERS, FABRICATORS AND INSTALLATION COMPANIES WHICH CAN DEMONSTRATE THEY POSSESS THE KNOWLEDGE, EXPERIENCE, AND PROVEN CAPABILITIES TO FULLY PERFORM ALL ASPECTS OF THE WORK REQUIRED WITHOUT OMISSION.
- 5. UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE PLOTTED IN THEIR APPROXIMATE LOCATIONS FROM THE BEST INFORMATION AVAILABLE TO THE ENGINEER. THE ENGINEER DOES NOT GUARANTEE THEIR ACCURACY OR GUARANTEE THAT ALL UTILITIES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES, INCLUDING ANY SUBSURFACE INVESTIGATIONS, AS MAY BE NECESSARY BEFORE ANY EXCAVATION IS PERFORMED.
- 6. THE CONTRACTOR SHALL CALL 811 48-HOURS BEFORE ANY EXCAVATION ACTIVITIES BEGIN TO HAVE UTILITIES LOCATED IN ACCORDANCE WITH STATE LAW. THE CONTRACTOR IS RESPONSIBLE FOR DAMAGES TO ALL UTILITIES DURING CONSTRUCTION. IF UTILITIES ARE DAMAGED THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE UTILITY INVOLVED IMMEDIATELY.
- 7. TEMPORARY BENCHMARK (T.B.M. = 367.18): SET PK NAIL IN GRASS ISLAND AT THE S/W CORNER OF THE INTERSECTION OF NEW CRAFT RD. AND HWY 178.
- 8. THIS PROPERTY IS LOCATED IN "ZONE X", AN AREA DETERMINED TO BE OUTSIDE THE 500-YEAR FLOOD PLAIN, ACCORDING TO FIRM COMMUNITY PANEL NO. 28095C0101D DATED MARCH 16, 1988. ELEVATIONS SHOWN HEREON WERE TAKEN ON THE GROUND USING T.B.M. NOTED HEREON.
- 9. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE FOR ENTIRE SITE. PONDING WATER WILL NOT BE ACCEPTED.
- 10. CONTRACTOR SHALL GRADE ALL ENTRANCE AND EXIT LANDINGS TO MATCH FINISHED FLOOR AND SLOPE AWAY FROM BUILDING AT -1.00%.
- 11. CONTRACTOR SHALL GRADE ALL SLOPES AS SHOWN TO A MINIMUM OF 3:1 SLOPE OR FLATTER.
- 12. SOME UTILITIES MAY REQUIRE DEMOLITION AND/OR RELOCATION. FOR DEMOLITION PLAN SEE SHEET C2.0. FOR UTILITY PLANS SEE SHEET C7.0.
- 13. CONTRACTOR SHALL FOLLOW GEOTECHNICAL REPORT FOR UNDERCUT AND SOIL PLACEMENT FOR BUILDING AND PARKING AREAS.




HOUSTON ENGINEERING
Engineering, Surveying, and Environmental Services


BRANCH, MS RADING PLAN N MANAGEMI HWY 178 I HWY178, OLIV ENLARGED


C4.2


8/9/22 ISSUE FOR REVIEW

JBH JBH










SCALE: 1" = 30'


GRADING & DRAINAGE PLAN NOTES:

- 1. THE CONTRACTOR SHALL COORDINATE AND OBTAIN ALL NECESSARY PERMITS AND APPROVALS OR GUIDELINES FROM GOVERNING REGULATORY AGENCIES BEFORE PROCEEDING WITH ANY ITEMS OF WORK UNDER OR WITHIN SUCH JURISDICTION(S).
- 2. ALL DIMENSIONS AND TIE-INS GOVERNED BY EXISTING CONDITIONS ARE APPROXIMATE AND ARE NOT GUARANTEED TO BE CORRECT. ALL SUCH DIMENSIONS AND CONDITIONS SHALL BE FIELD VERIFIED BY THE GENERAL CONTRACTOR PRIOR TO PROCEEDING WITH ANY WORK. IF CONDITIONS AND DIMENSIONS VARY FROM THOSE SHOWN, THE CONTRACTOR SHALL NOTIFY THE ENGINEER BEFORE PROCEEDING WITH WORK WHERE DIMENSIONS ARE NOT SHOWN WITH +/- INDICATIONS ADJUSTMENTS MAY BE MADE TO SUIT FIELD CONDITIONS.
- 3. THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS, LOCATION OF UTILITY SERVICES, DIMENSIONS, AND ELEVATIONS OF SITE AND ANY DATA REQUIRED TO CONSTRUCT THE PROJECT.
- 4. THE CONTRACTOR SHALL SUBCONTRACT WITH SUPPLIERS, FABRICATORS AND INSTALLATION COMPANIES WHICH CAN DEMONSTRATE THEY POSSESS THE KNOWLEDGE, EXPERIENCE, AND PROVEN CAPABILITIES TO FULLY PERFORM ALL ASPECTS OF THE WORK REQUIRED WITHOUT OMISSION.
- 5. UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE PLOTTED IN THEIR APPROXIMATE LOCATIONS FROM THE BEST INFORMATION AVAILABLE TO THE ENGINEER. THE ENGINEER DOES NOT GUARANTEE THEIR ACCURACY OR GUARANTEE THAT ALL UTILITIES ARE SHOWN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES, INCLUDING ANY SUBSURFACE INVESTIGATIONS, AS MAY BE NECESSARY BEFORE ANY EXCAVATION IS PERFORMED.
- 6. THE CONTRACTOR SHALL CALL 811 48-HOURS BEFORE ANY EXCAVATION ACTIVITIES BEGIN TO HAVE UTILITIES LOCATED IN ACCORDANCE WITH STATE LAW. THE CONTRACTOR IS RESPONSIBLE FOR DAMAGES TO ALL UTILITIES DURING CONSTRUCTION. IF UTILITIES ARE DAMAGED THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE UTILITY INVOLVED IMMEDIATELY.
- 7. TEMPORARY BENCHMARK (T.B.M. = 367.18): SET PK NAIL IN GRASS ISLAND AT THE S/W CORNER OF THE INTERSECTION OF NEW CRAFT RD. AND HWY 178.
- 8. THIS PROPERTY IS LOCATED IN "ZONE X", AN AREA DETERMINED TO BE OUTSIDE THE 500-YEAR FLOOD PLAIN, ACCORDING TO FIRM COMMUNITY PANEL NO. 28095C0101D DATED MARCH 16, 1988. ELEVATIONS SHOWN HEREON WERE TAKEN ON THE GROUND USING T.B.M. NOTED HEREON.
- 9. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE FOR ENTIRE SITE. PONDING WATER WILL NOT BE ACCEPTED.
- 10. CONTRACTOR SHALL GRADE ALL ENTRANCE AND EXIT LANDINGS TO MATCH FINISHED FLOOR AND SLOPE AWAY FROM BUILDING AT -1.00%.
- 11. CONTRACTOR SHALL GRADE ALL SLOPES AS SHOWN TO A MINIMUM OF 3:1 SLOPE OR FLATTER.
- 12. SOME UTILITIES MAY REQUIRE DEMOLITION AND/OR RELOCATION. FOR DEMOLITION PLAN SEE SHEET C2.0. FOR UTILITY PLANS SEE SHEET C7.0.
- 13. CONTRACTOR SHALL FOLLOW GEOTECHNICAL REPORT FOR UNDERCUT AND SOIL PLACEMENT FOR BUILDING AND PARKING AREAS.



HOUSTON ENGINEERING

Engineering, Surveying, and Environmental Services





AN MANAGEMENT COMPANY, I HWY 178 FUEL CENTER O HWY178, OLIVE BRANCH, MS 3 ENLARGED DRAINAGE PLAN


C5.2

8/9/22 ISSUE FOR REVIEW

JBH JBH








A 9/12/22 ISSUE FOR REVIEW

JBH JBH

HOUSTON ENGINEERING


Engineering, Surveying, and Environmental Services





N MANAGEMENT COMPANY, I HWY 178 FUEL CENTER HWY178, OLIVE BRANCH, MS 3 SITE UTILITY PLAN



19 - C7.0








8/9/22 ISSUE FOR REVIEW

JBH JBH

BY APVD



SCALE: 1" = 50'

STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

Site Information

The construction of a commercial building and associated pavements will disturb 7.25 acres. Three- fourths of this site has a medium erosion hazard. The remainder of the site has 10 to 20 percent slopes that are highly erodible. The site drains to a road ditch adjacent to Highway 178 and to a ditch through the property and on to Johns Creek which is not on the 303(d) list for siltation, turbidity or habitat alterations, therefore additional controls that are warranted for a site discharging to listed receiving streams are not required.

Vegetative Controls: A 15-foot undisturbed vegetative buffer zone will be maintained around the perimeter of the site. Existing trees will be preserved where possible. All diversions will be seeded (permanent seeding) within seven calendar days of construction. Topsoil will be stockpiled for use in landscaping.

Grass-lined waterways will be constructed and lined with temporary straw-net liners and will be constructed around the building. All 3:1 cut slopes will be roughened by disking prior to seeding. Slopes steeper than 6:1 slope will be soddened with Bermuda grass. Any disturbed areas that will be left undisturbed for 14 or more days will be seeded (temporary seeding) immediately, meaning no later than the following day. After final grading, all disturbed areas will be seeded (permanent seeding) immediately, meaning no later than the following day.

Structural Controls: A sediment basin with a drop inlet discharge will be constructed at the northern end of the project. sediment basin will be constructed at the southwest corner of the property where runoff leaves the property. Storm water will be directed to these basins with the assistance of diversions and grassed waterways. Upslope waters will be diverted around disturbed areas. All cut slopes will be at or below a 3:1 grade. A construction entrance will be built and any accumulation of mud on vehicle tires will be washed, if needed, during muddy conditions. Inlet protection (silt fences) will be installed at all storm drain inlets. A silt fence will be constructed around the stockpile. Riprap will be placed at all culvert outlet aprons. A sediment pit will be excavated for concrete trucks to wash the mixer chutes and a memo will be sent to the concrete supplier to use a minimum amount of water. Drivers will be instructed to return any materials to the concrete batch plant and complete final washing procedures at that location.

Housekeeping Practices. All equipment maintenance and repair will be done offsite. Trash cans will be placed at convenient locations throughout the site. The main trash collection bin will be located on the northeast corner of the site and will be picked up weekly by the city. Paints, solvents, fertilizers, or any other potentially toxic materials will not be stored onsite. Portable sanitary facilities will be provided for construction workers. There is a marked and designated area for concrete truck wash off.

Post Construction/Storm Water Management Measures: The temporary sediment basin will be converted to a detention basin after construction. Riprap will be placed at concentrated storm water discharge points to prevent erosion from high runoff velocities.

Implementation Sequence

- 1) Build construction entrance/exit.
- 2) Install silt fence around excavation limits without disturbing Buffer Zones.
- 3) Clear and Grub areas to be graded using Best Management Practices.
- 4) Construct sediment basins. Grade site and begin building construction to lines as shown on plans. Place wattles as needed to control erosion.
- 5) Construct parking areas with pipes and inlets as shown on the plans. Install riprap as shown at the end of pipe
- 6) Install roof drain collection as shown on the plans complete with energy dissipaters.
- 7) Plant temporary vegetation as necessary to prevent sedimentation and to protect slopes. (Temporary Mulch weekly) 8) Finish grade all slopes and backfill curbs.
- 9) Plant permanent vegetation and landscaping per plans.
- 10) After site is stabilized, remove temporary measures, vegetate additional areas as required.

Maintenance Plan

Check all disturbed areas, erosion, and sediment controls after each significant rainfall but not less than once per week. Make needed repairs within 24 hours. Remove sediment from the basin, inlet protection devices and silt fences when accumulated sediment has reached 50 percent capacity. Replace non-functional silt fence. Maintain all vegetated areas to provide proper ground cover - reseed, fertilize, and mulch as needed. Erosion control measures and monitoring shall be completed under the direction of QCP qualified personnel.

CONTRACTOR SHALL KEEP SILT AND MUD FROM ENTERING THE HIGHWAY. THE CONTRACTOR SHALL PROVIDE EQUIPMENT (STREET SWEEPER) NECESSARY TO KEEP THE HIGHWAY CLEAN DURING CONSTRUCTION

LEGEND:

SILT FENCE

WATTLE WATER RELEASE

ROCK CHECK DAM

WATTLE DITCH CHECK WATTLE INLET PROTECTION - CURB

RIPRAP


C9.0


HOUSTON ENGINEERING


Engineering, Surveying, and Environmental Services


/E BRANCH, MS 38 I CONTROL PLAN

N MANAGEM HWY 178 HWY178, OL SITE EROSIC










3/21/22 ISSUE FOR REVIEW

JBH JBH

HOUSTON ENGINEERING





N MANAGEMEI HWY 178 F HWY178, OLIVI MISCELLANE 0


222-157.015
3UNE 2022
B. HOUSTON
K.R. McCACHRE
B. HOUSTON
B. HOUSTON

SCALE:
JOB NO.
DATE:
DSGN.:
DWG. B'
CHK.:


D4.0








JBH JBH BY APVD



TYPE B SILT BASIN D8.0 SCALE: N.T.S.

HOUSTON Fngineering, Surveyi



GEN178
3, OL HWY178 TYPE

D8.0

A 8/9/22 ISSUE FOR REVIEW

ЈВН ЈВН

STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

Site Information

The construction of a commercial building and associated pavements will disturb 7.25 acres. Three-fourths of this site has a medium erosion hazard. The remainder of the site has 10 to 20 percent slopes that are highly erodible. The site drains to a road ditch adjacent to Highway 178 and to a ditch through the property and on to Johns Creek which is not on the 303(d) list for siltation, turbidity or habitat alterations, therefore additional controls that are warranted for a site discharging to listed receiving streams are not required.

Controls

Vegetative Controls: A 15-foot undisturbed vegetative buffer zone will be maintained around the perimeter of the site. Existing trees will be preserved where possible. All diversions will be seeded (permanent seeding) within seven calendar days of construction. Topsoil will be stockpiled for use in landscaping. Grass-lined waterways will be constructed and lined with temporary straw-net liners and will be constructed around the building. All 3:1 cut slopes will be roughened by disking prior to seeding. Slopes steeper than 6:1 slope will be soddened with Bermuda grass. Any disturbed areas that will be left undisturbed for 14 or more days will be seeded (temporary seeding) <u>immediately</u>, meaning no later than the following day. After final grading, all disturbed areas will be seeded (permanent seeding) <u>immediately</u>, meaning no later than the following day.

Structural Controls: A sediment basin with a drop inlet discharge will be constructed at the northern end of the project. Storm water will be directed to said basin with the assistance of diversions, grassed waterways, and storm drainpipes. Upslope waters will be diverted around disturbed areas. All cut slopes will be at or below a 3:1 grade. A construction entrance will be built and any accumulation of mud on vehicle tires will be washed, if needed, during muddy conditions. Inlet protection (silt fences) will be installed at all storm drain inlets. A silt fence will be constructed around the topsoil stockpile. Geotextile Fabric and riprap will be placed at all culvert outlet aprons. A sediment pit will be excavated for concrete trucks to wash the mixer chutes and a memo will be sent to the concrete supplier to use a minimum amount of water. Drivers will be instructed to return any materials to the concrete batch plant and complete final washing procedures at that location.

Housekeeping Practices. All equipment maintenance and repair will be done offsite. Trash cans will be placed at convenient locations throughout the site. The main trash collection bin will be located on the northeast corner of the site and will be picked up weekly by the city. Paints, solvents, fertilizers, or any other potentially toxic materials will not be stored onsite. Portable sanitary facilities will be provided for construction workers. There is a marked and designated area for concrete truck wash off.

Post Construction/Storm Water Management Measures: The temporary sediment basin will be converted to a detention basin after construction. Riprap will be placed at concentrated storm water discharge points to prevent erosion from high runoff velocities.

Implementation Sequence

- 1) Build construction entrance/exit.
- 2) Install silt fence around excavation limits without disturbing Buffer Zones.
- 3) Clear and Grub areas to be graded using Best Management Practices.
- 4) Construct sediment basins. Grade site and begin building construction to lines as shown on plans. Place wattles as needed to control erosion.A
- 5) Construct parking areas with pipes and inlets as shown on the plans. Install riprap as shown at the end of pipe outfalls.
- 6) Install roof drain collection as shown on the plans complete with energy dissipaters.
- 7) Plant temporary vegetation as necessary to prevent sedimentation and to protect slopes. (Temporary Mulch weekly)
- 8) Finish grade all slopes and backfill curbs.
- 9) Plant permanent vegetation and landscaping per plans.
- 10) After site is stabilized, remove temporary measures, vegetate additional areas as required.

Maintenance Plan

Check all disturbed areas, erosion, and sediment controls after each significant rainfall but not less than once per week. Make needed repairs within 24 hours. Remove sediment from the basin, inlet protection devices and silt fences when accumulated sediment has reached 50 percent capacity. Replace non-functional silt fence. Maintain all vegetated areas to provide proper ground cover - reseed, fertilize, and mulch as needed. Erosion control measures and monitoring shall be completed under the direction of QCP qualified personnel.